


# PUT TURRET BOLTS TO PROPER USE



The 11 bolts, NSN 5305-01-014-5124, on top of your tank's turret are there for a reason, crewmen. And it's not for mounting flag brackets, road-wheels, lights or any other hardware.

Those bolts protect the threads inside each of the holes where the turret lifting device is attached. Mess up the threads and there's no way to separate the turret from the hull for support-level repairs.

If you've removed any of the bolts or some come up missing, check the holes to make sure they're clean and free of debris. Then, add a little antiseize compound, NSN 8030-00-597-5367, to the threads before reinstalling the bolt. That prevents corrosion and reduces wear and tear on the threads.

